Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
		2nd cross Sapthagiri hall								
0	15		Sqm	1	15.00	4.65		69.75		
15	30		Sqm	1	15.00	3.80		57.00		
30	45		Sqm	1	15.00	3.10		46.50		
45	60		Sqm	1	15.00	3.30		49.50		
60	75		Sqm	1	15.00	3.70		55.50		
75	85		Sqm	1	10.00	4.10		41.00		
		Near Under Pass (Pot hole)								
0	13		Sqm	1	13.00	5.20		67.60		
13	22		Sqm	1	9.00	5.00		45.00		
28	39		Sqm	1	11.00	3.30		36.30		
47	52		Sqm	1	5.00	4.50		22.50		
77	86		Sqm	1	9.00	2.00		18.00		
		kodige Halli Near Sanu Boga narayanappa layout								
0	20		Sqm	1	20.00	2.50		50.00		
		1st main								
0	15		Sqm	1	15.00	5.55		83.25		
15	30		Sqm	1	15.00	5.20		78.00		
30	45		Sqm	1	15.00	5.45		81.75		
45	60		Sqm	1	15.00	5.35		80.25		
60	75		Sqm	1	15.00	5.40		81.00		
75	90		Sqm	1	15.00	5.70		85.50		
90	105		Sqm	1	15.00	5.70		85.50		
105	120		Sqm	1	15.00	5.65		84.75		
120	135		Sqm	1	15.00	5.80		87.00		
135	149		Sqm	1	14.00	5.95		83.30		
		1st A main								
0	15		Sqm	1	15.00	5.70		85.50		
15	30		Sqm	1	15.00	5.15		77.25		
30	45		Sqm	1	15.00	4.45		66.75		
45	60		Sqm	1	15.00	4.30		64.50		
60	75		Sqm	1	15.00	4.30		64.50		
75	90		Sqm	1	15.00	4.40		66.00		
90	105		Sqm	1	15.00	4.50		67.50		
105	120		Sqm	1	15.00	4.65		69.75		
120	135		Sqm	1	15.00	5.30		79.50		
135	142		Sqm	1	7.00	5.70		39.90		
		Dr Rajgopal road kodigehalli								
		Culvert to kodigehalli Circle	Sqm	1	50.50	16.80		848.40		
		Culvert to Underpass	Sqm	1	138.30	16.10		2226.63		
		Tata Nagar								
		5th Cross	Sqm	1	307.00	7.00		2149.00		
		3rd main Road	Sqm	1	139.00	6.80		945.20		
		Infront Of Little wonder								
0	15		Sqm	1	15.00	6.50		97.50		
15	30		Sqm	1	15.00	6.40		96.00		
30	45		Sqm	1	15.00	6.40		96.00		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
30	60		Sqm	1	30.00	5.10		153.00		
60	90		Sqm	1	30.00	4.95		148.50		
90	120		Sqm	1	30.00	4.90		147.00		
120	150		Sqm	1	30.00	4.80		144.00		
150	180		Sqm	1	30.00	4.55		136.50		
180	210		Sqm	1	30.00	4.70		141.00		
210	240		Sqm	1	30.00	4.95		148.50		
240	270		Sqm	1	30.00	5.15		154.50		
270	297		Sqm	1	27.00	5.85		157.95		
		3rd cross								
0	30		Sqm	1	30.00	4.18		125.25		
30	60		Sqm	1	30.00	4.48		134.25		
60	90		Sqm	1	30.00	4.48		134.25		
90	120		Sqm	1	30.00	4.40		132.00		
120	150		Sqm	1	30.00	4.40		132.00		
150	180		Sqm	1	30.00	4.25		127.50		
180	213		Sqm	1	33.10	5.58		184.53		
		4th cross								
0	30		Sqm	1	30.00	3.88		116.25		
30	60		Sqm	1	30.00	3.85		115.50		
60	90		Sqm	1	30.00	3.85		115.50		
90	120		Sqm	1	30.00	3.53		105.75		
120	150		Sqm	1	30.00	3.35		100.50		
150	180		Sqm	1	30.00	3.18		95.25		
180	210		Sqm	1	30.00	3.33		99.75		
210	225		Sqm	1	15.00	3.50		52.50		
		SIR M.V. LAYOUT								
		2nd main 3rd cross road								
0	30		Sqm	1	30.00	4.70		141.00		
30	60		Sqm	1	30.00	3.90		117.00		
60	90		Sqm	1	30.00	4.75		142.50		
90	120		Sqm	1	30.00	5.20		156.00		
120	150		Sqm	1	30.00	4.75		142.50		
150	180		Sqm	1	30.00	4.75		142.50		
180	210		Sqm	1	30.00	4.65		139.50		
210	240		Sqm	1	30.00	4.70		141.00		
240	272		Sqm	1	32.00	4.90		156.80		
		2nd main 6th cross road								
0	30		Sqm	1	30.00	5.15		154.50		
30	60		Sqm	1	30.00	4.25		127.50		
60	90		Sqm	1	30.00	4.40		132.00		
90	118		Sqm	1	27.70	5.15		142.66		
		Opposite 6th Cross Road								
0	30		Sqm	1	30.00	4.05		121.50		
30	60		Sqm	1	30.00	4.25		127.50		
60	90		Sqm	1	30.00	4.25		127.50		
		2nd main 7'A cross road								
0	30		Sqm	1	30.00	4.75		142.50		
30	60		Sqm	1	30.00	4.45		133.50		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
120	150		Sqm	1	30.00	4.55		136.50		
150	180		Sqm	1	30.00	4.85		145.50		
180	205		Sqm	1	25.00	4.70		117.50		
205	235		Sqm	1	30.00	4.80		144.00		
235	265		Sqm	1	30.00	4.80		144.00		
265	295		Sqm	1	30.00	4.45		133.50		
295	315		Sqm	1	20.00	4.90		98.00		
		1st main, 4th cross road near satya green appartment								
0	30		Sqm	1	30.00	4.75		142.50		
30	60		Sqm	1	30.00	4.50		135.00		
60	90		Sqm	1	30.00	4.60		138.00		
90	120		Sqm	1	30.00	4.60		138.00		
120	150		Sqm	1	30.00	4.45		133.50		
150	175		Sqm	1	25.00	4.15		103.75		
		Cross road								
0	40		Sqm	1	40.00	5.55		222.00		
		Cross road								
0	40		Sqm	1	40.00	4.90		196.00		
		5th A cross								
0	30		Sqm	1	30.00	5.00		150.00		
30	60		Sqm	1	30.00	5.05		151.50		
60	88.1		Sqm	1	28.10	5.05		141.91		
		IEHCS LAYOUT								
		6th A Main Road								
0	30		Sqm	1	30.00	5.70		171.00		
30	60		Sqm	1	30.00	5.40		162.00		
60	90		Sqm	1	30.00	5.20		156.00		
90	120		Sqm	1	30.00	5.60		168.00		
120	150		Sqm	1	30.00	6.10		183.00		
150	180		Sqm	1	30.00	5.75		172.50		
180	208		Sqm	1	27.80	5.55		154.29		
		7th Main Road								
0	15		Sqm	1	15.00	4.60		69.00		
15	30		Sqm	1	15.00	4.60		69.00		
30	45		Sqm	1	15.00	4.60		69.00		
45	60		Sqm	1	15.00	4.60		69.00		
60	75		Sqm	1	15.00	4.60		69.00		
75	90		Sqm	1	15.00	4.60		69.00		
90	105		Sqm	1	15.00	4.65		69.75		
105	120		Sqm	1	15.00	4.75		71.25		
120	135		Sqm	1	15.00	4.65		69.75		
135	150		Sqm	1	15.00	4.45		66.75		
150	165		Sqm	1	15.00	4.45		66.75		
165	180		Sqm	1	14.90	4.85		72.27		
		7th A Main Road								
0	15		Sqm	1	15.00	6.30		94.50		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
15	30		Sqm	1	15.00	4.90		73.50		
30	45		Sqm	1	15.00	4.90		73.50		
45	60		Sqm	1	15.00	4.95		74.25		
60	75		Sqm	1	15.00	5.00		75.00		
75	90		Sqm	1	15.00	4.95		74.25		
90	105		Sqm	1	15.00	4.90		73.50		
105	120		Sqm	1	15.00	4.85		72.75		
120	135		Sqm	1	15.00	4.90		73.50		
135	150		Sqm	1	15.00	4.95		74.25		
150	165		Sqm	1	15.00	4.90		73.50		
165	180		Sqm	1	15.00	4.90		73.50		
180	194		Sqm	1	13.70	5.45		74.66		
		1st Cross Road								
0	15		Sqm	1	15.00	6.05		90.75		
15	30		Sqm	1	15.00	4.80		72.00		
30	45		Sqm	1	15.00	4.55		68.25		
45	60		Sqm	1	15.00	4.45		66.75		
60	75		Sqm	1	15.00	4.45		66.75		
75	90		Sqm	1	15.00	4.50		67.50		
90	105		Sqm	1	15.00	4.70		70.50		
105	120		Sqm	1	15.00	4.70		70.50		
120	134		Sqm	1	13.90	5.90		82.01		
		GURUDARSHAN LAYOUT								
		5th Cross Road								
0	30		Sqm	1	30.00	4.50		135.00		
30	60		Sqm	1	30.00	4.70		141.00		
60	90		Sqm	1	30.00	4.85		145.50		
90	105		Sqm	1	14.80	4.80		71.04		
		6th Cross Road								
0	30		Sqm	1	30.00	4.80		144.00		
30	60		Sqm	1	30.00	4.90		147.00		
60	90		Sqm	1	30.00	4.85		145.50		
90	104		Sqm	1	14.30	4.85		69.36		
		7th Cross Road								
0	30		Sqm	1	30.00	4.80		144.00		
30	60		Sqm	1	30.00	4.15		124.50		
60	90		Sqm	1	30.00	4.20		126.00		
90	105		Sqm	1	14.50	4.80		69.60		
		Kempegowda nagara main road								
0	15		sqm	1	15.00	5.55		83.25		
15	30		sqm	1	15.00	5.55		83.25		
30	45		sqm	1	15.00	5.50		82.50		
45	60		sqm	1	15.00	5.45		81.75		
60	75		sqm	1	15.00	5.40		81.00		
75	90		sqm	1	15.00	5.50		82.50		
90	105		sqm	1	15.00	5.25		78.75		
105	120		sqm	1	15.00	5.20		78.00		
120	135		sqm	1	15.00	5.80		87.00		
135	150		sqm	1	15.00	5.85		87.75		
150	171		sqm	1	21.00	5.90		123.90		
171	186		sqm	1	15.00	6.20		93.00		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
65	80		Cum	1	15.00	4.85	0.04	2.91		
80	95		Cum	1	15.00	4.35	0.04	2.61		
95	110		Cum	1	15.00	4.25	0.04	2.55		
110	130		Cum	1	15.00	4.50	0.04	2.70		
130	155.5		Cum	1	15.00	4.60	0.04	2.76		
		3rd Cross Road	Cum	1	13.20	5.00	0.04	2.44		
0	15									
15	30		Cum	1	15.00	5.15	0.04	3.09		
30	45		Cum	1	15.00	3.75	0.04	2.25		
45	60		Cum	1	15.00	4.15	0.04	2.49		
60	75		Cum	1	15.00	4.45	0.04	2.67		
75	90		Cum	1	15.00	4.50	0.04	2.70		
90	105		Cum	1	15.00	4.70	0.04	2.82		
105	120		Cum	1	15.00	4.70	0.04	2.82		
120	135		Cum	1	15.00	4.65	0.04	2.79		
135	150		Cum	1	15.00	4.65	0.04	2.79		
150	165		Cum	1	15.00	4.75	0.04	2.85		
		4th cross road	Cum	1	7.00	5.15	0.04	1.44		
0	15									
15	30		Cum	1	15.00	6.50	0.04	3.90		
30	45		Cum	1	15.00	4.80	0.04	2.88		
45	60		Cum	1	15.00	4.80	0.04	2.88		
60	75		Cum	1	15.00	4.80	0.04	2.88		
75	90		Cum	1	15.00	4.65	0.04	2.79		
90	105		Cum	1	15.00	4.50	0.04	2.70		
105	120		Cum	1	15.00	4.65	0.04	2.79		
120	135		Cum	1	15.00	5.05	0.04	3.03		
135	150		Cum	1	15.00	4.70	0.04	2.82		
150	165		Cum	1	15.00	4.70	0.04	2.82		
165	181		Cum	1	16.00	4.70	0.04	3.01		
		2nd cross road								
0	15		Cum	1	15.00	6.40	0.04	3.84		
15	30		Cum	1	15.00	5.85	0.04	3.51		
30	45		Cum	1	15.00	5.40	0.04	3.24		
45	60		Cum	1	15.00	5.25	0.04	3.15		
60	75		Cum	1	15.00	5.50	0.04	3.30		
75	90		Cum	1	15.00	5.40	0.04	3.24		
90	105		Cum	1	15.00	5.35	0.04	3.21		
105	120		Cum	1	15.00	5.75	0.04	3.45		
120	128.8		Cum	1	6.80	6.20	0.04	1.69		
		3rd Cross Rd								
0	15		Cum	1	15.00	5.45	0.04	3.27		
15	30		Cum	1	15.00	4.40	0.04	2.64		
30	46		Cum	1	16.00	4.20	0.04	2.69		
		7th Cross road								
0	15		Cum	1	15.00	5.60	0.04	3.36		
15	30		Cum	1	15.00	4.60	0.04	2.76		
30	45		Cum	1	15.00	5.80	0.04	3.48		
45	60		Cum	1	15.00	6.80	0.04	4.08		
60	75		Cum	1	15.00	5.70	0.04	3.42		
75	90		Cum	1	15.00	4.65	0.04	2.79		
90	105		Cum	1	15.00	4.45	0.04	2.67		
105	120		Cum	1	15.00	4.40	0.04	2.64		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		20thC (7th main to 2nd main road-hello kids)								
0	15		Cum	1	15.00	6.35	0.04	3.81		
15	30		Cum	1	15.00	5.90	0.04	3.54		
30	45		Cum	1	15.00	5.75	0.04	3.45		
45	60		Cum	1	15.00	5.70	0.04	3.42		
60	75		Cum	1	15.00	5.30	0.04	3.18		
75	90		Cum	1	15.00	5.15	0.04	3.09		
90	105		Cum	1	15.00	5.55	0.04	3.33		
105	120		Cum	1	15.00	5.95	0.04	3.57		
120	135		Cum	1	15.00	5.30	0.04	3.18		
135	150		Cum	1	15.00	5.05	0.04	3.03		
150	165		Cum	1	15.00	5.60	0.04	3.36		
165	180		Cum	1	15.00	5.20	0.04	3.12		
180	196		Cum	1	16.00	5.60	0.04	3.58		
		2nd main (20th C cross to 21st C cross								
0	15		Cum	1	15.00	8.60	0.04	5.16		
15	30		Cum	1	15.00	8.15	0.04	4.89		
30	45		Cum	1	15.00	7.90	0.04	4.74		
45	60		Cum	1	15.00	7.55	0.04	4.53		
60	75		Cum	1	15.00	7.85	0.04	4.71		
75	90		Cum	1	15.00	8.40	0.04	5.04		
90	105		Cum	1	15.00	8.05	0.04	4.83		
105	120		Cum	1	15.00	7.90	0.04	4.74		
120	135		Cum	1	15.00	8.05	0.04	4.83		
135	148		Cum	1	13.00	7.80	0.04	4.06		
148	163		Cum	1	15.00	5.65	0.04	3.39		
163	178		Cum	1	15.00	5.50	0.04	3.30		
178	193		Cum	1	15.00	5.75	0.04	3.45		
193	207		Cum	1	14.00	6.40	0.04	3.58		
		1st A in 20th A main CQAL lyt								
0	15		Cum	1	15.00	6.00	0.04	3.60		
15	30		Cum	1	15.00	5.95	0.04	3.57		
30	45		Cum	1	15.00	5.80	0.04	3.48		
		1st B in 20th A main CQAL lyt								
0	15		Cum	1	15.00	5.70	0.04	3.42		
15	30		Cum	1	15.00	5.70	0.04	3.42		
30	47		Cum	1	17.00	5.65	0.04	3.84		
		20th E cross road, 1st main								
0	15		Cum	1	15.00	5.30	0.04	3.18		
15	30		Cum	1	15.00	5.85	0.04	3.51		
30	48		Cum	1	18.00	5.50	0.04	3.96		
		3rd main C block								
0	15		Cum	1	15.00	5.30	0.04	3.18		
15	30		Cum	1	15.00	5.75	0.04	3.45		
30	45		Cum	1	15.00	6.05	0.04	3.63		
45	60		Cum	1	15.00	6.25	0.04	3.75		
60	75		Cum	1	15.00	6.50	0.04	3.90		
75	90		Cum	1	15.00	6.35	0.04	3.81		
90	105		Cum	1	15.00	6.05	0.04	3.63		
105	120		Cum	1	15.00	5.90	0.04	3.54		
120	130		Cum	1	10.00	5.75	0.04	2.30		
		6th main								
0	15		Cum	1	15.00	6.20	0.04	3.72		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
30	60		Cum	1	30.00	4.35	0.04	0.52		
60	90		Cum	1	30.00	4.25	0.04	0.51		
90	120		Cum	1	30.00	4.50	0.04	0.54		
120	136		Cum	1	16.30	4.30	0.04	0.28		
		3rd D cross road								
0	15		Cum	1	15.00	6.10	0.04	0.37		
15	30		Cum	1	15.00	5.05	0.04	0.30		
30	45		Cum	1	15.00	3.35	0.04	0.20		
45	60		Cum	1	15.00	3.70	0.04	0.22		
60	75		Cum	1	15.00	4.70	0.04	0.28		
75	90		Cum	1	15.00	4.55	0.04	0.27		
90	105		Cum	1	15.00	4.25	0.04	0.26		
		3rd A cross road								
0	30		Cum	1	30.00	5.40	0.04	0.65		
30	68		Cum	1	38.00	5.40	0.04	0.82		
		opposite to 3rd A cross road								
0	33.9		Cum	1	33.90	4.25	0.04	0.58		
		3rd' E cross road								
0	30		Cum	1	30.00	3.70	0.04	0.44		
30	55		Cum	1	25.00	3.85	0.04	0.39		
		UAS appartment								
0	30		Cum	1	30.00	6.35	0.04	0.76		
30	60		Cum	1	30.00	4.35	0.04	0.52		
60	90		Cum	1	30.00	6.25	0.04	0.75		
90	120		Cum	1	30.00	6.20	0.04	0.74		
120	150		Cum	1	30.00	4.55	0.04	0.55		
150	180		Cum	1	30.00	4.65	0.04	0.56		
180	203		Cum	1	23.00	4.85	0.04	0.45		
		1st cross (from dead end)								
0	29		Cum	1	29.00	4.65	0.04	0.54		
		2nd Cross								
0	18.5		Cum	1	18.50	4.50	0.04	0.33		
		3rd Cross								
0	17.8		Cum	1	17.80	4.00	0.04	0.28		
		4th Cross								
0	32.7		Cum	1	32.70	4.80	0.04	0.63		
		5th Cross								
0	16.5		Cum	1	16.50	3.90	0.04	0.26		
16.5	25.2		Cum	1	8.70	2.65	0.04	0.09		
		6th Cross								
0	32.1		Cum	1	32.10	4.30	0.04	0.55		
		VMS garden 1st cross								
		('T' cross road) & T								
0	15		Cum	1	15.00	5.15	0.04	0.31		
15	30		Cum	1	15.00	5.75	0.04	0.35		
30	45		Cum	1	15.00	5.50	0.04	0.33		
45	60		Cum	1	15.00	5.15	0.04	0.31		
60	75		Cum	1	15.00	5.25	0.04	0.32		
75	90		Cum	1	15.00	5.35	0.04	0.32		
90	105		Cum	1	15.00	5.50	0.04	0.33		
105	120		Cum	1	15.00	5.65	0.04	0.34		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
		2nd cross road								
0	30		Cum	1	30.00	6.30	0.04	7.56		
30	38		Cum	1	8.00	6.85	0.04	2.19		
		9th to 8th cross road								
0	25		Cum	1	25.00	3.40	0.04	3.40		
		8th cross								
0	30		Cum	1	30.00	4.90	0.04	5.88		
30	60		Cum	1	30.00	5.05	0.04	6.06		
60	90		Cum	1	30.00	5.15	0.04	6.18		
90	120		Cum	1	30.00	5.50	0.04	6.60		
120	139		Cum	1	18.80	6.10	0.04	4.59		
		7th cross								
0	30		Cum	1	30.00	4.65	0.04	5.58		
30	60		Cum	1	30.00	4.45	0.04	5.34		
60	90		Cum	1	30.00	4.15	0.04	4.98		
90	109		Cum	1	19.20	3.95	0.04	3.03		
		2nd main, 2nd cross road								
0	30		Cum	1	30.00	4.20	0.04	5.04		
30	60		Cum	1	30.00	4.10	0.04	4.92		
60	90		Cum	1	30.00	4.35	0.04	5.22		
90	120		Cum	1	30.00	4.40	0.04	5.28		
120	150		Cum	1	30.00	4.55	0.04	5.46		
150	180		Cum	1	30.00	4.85	0.04	5.82		
180	205		Cum	1	25.00	4.70	0.04	4.70		
205	235		Cum	1	30.00	4.80	0.04	5.76		
235	265		Cum	1	30.00	4.80	0.04	5.76		
265	295		Cum	1	30.00	4.45	0.04	5.34		
295	315		Cum	1	20.00	4.90	0.04	3.92		
		1st main, 4th cross road near satya green appartment								
0	30		Cum	1	30.00	4.75	0.04	5.70		
30	60		Cum	1	30.00	4.50	0.04	5.40		
60	90		Cum	1	30.00	4.60	0.04	5.52		
90	120		Cum	1	30.00	4.60	0.04	5.52		
120	150		Cum	1	30.00	4.45	0.04	5.34		
150	175		Cum	1	25.00	4.15	0.04	4.15		
		Cross road	Cum							
0	40			1	40.00	5.55	0.04	8.88		
		Cross road	Cum							
0	40		Cum	1	40.00	4.90	0.04	7.84		
		5th A cross								
0	30		Cum	1	30.00	5.00	0.04	6.00		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate	Amount
From	To								Rs	Rs
0	104									
		5th Cross Road	Sqm	2	104.30	0.10		20.86		
		Edge line								
0	105									
		Kempegowda Nagara Main road	Sqm	2	104.50	0.10		20.90		
		Edge line								
0	186									
		5th cross road	Sqm	2	186.00	0.10		37.20		
		Kempegowda nagara								
		Edge line								
0	40									
		Vanni court road	Sqm	2	40.00	0.10		8.00		
		Edge line								
0	194									
		2nd Block 13th Main	Sqm	2	194.00	0.10		38.80		
		Road								
		Edge line								
0	80									
		1st Block 13th Main	Sqm	2	188.00	0.10		37.60		
		Road								
		Edge line								
0	187									
		1st Block 8th Main	Sqm	2	187.20	0.10		37.44		
		Road								
		Edge line								
0	153									
		1st Block 14th Main	Sqm	2	152.90	0.10		30.58		
		Road								
		Edge line								
0	139									
		2nd Block 13th Main	Sqm	2	139.10	0.10		27.82		
		Road								
		Edge line								
0	245									
		2nd Block 3rd Cross	Sqm	2	245.20	0.10		49.04		
		Road								
		Edge line								
0	135									
		2nd Block 5th Cross	Sqm	2	134.50	0.10		26.90		
		Road								
		Edge line								
0	180									
		2nd Block 7th Cross	Sqm	2	180.00	0.10		36.00		
		Road								
		Edge line								
0	193									
		2nd Block 8th Cross	Sqm	2	192.60	0.10		38.52		
		Road								
		Edge line								
0	185									
		Un named Road	Sqm	2	185.00	0.10		37.00		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		5th cross RK Layourt								
		Edge line								
0	64		sqm	2	64.00	0.10		12.80		
		5thA main RK Layout								
		Edge line								
0	101		sqm	2	101.00	0.10		20.20		
		5th main RK Layout								
		Edge line								
0	220		sqm	2	220.00	0.10		44.00		
							Total Qty	3461.99	580.71	2010412.10
							Tender Qty	4320.791		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
45	54		Cum	1	9.00	0.90	0.125	1.01		
		Right Side								
0	15		Cum	1	15.00	0.90	0.125	1.69		
15	30		Cum	1	15.00	0.90	0.125	1.69		
30	46		Cum	1	16.00	0.90	0.125	1.80		
		4th Cross road								
		Left Side								
0	15		Cum	1	15.00	0.90	0.125	1.69		
15	30		Cum	1	15.00	0.90	0.125	1.69		
30	45		Cum	1	15.00	0.90	0.125	1.69		
45	54		Cum	1	9.00	0.90	0.125	1.01		
		Right Side								
0	15		Cum	1	15.00	0.90	0.125	1.69		
15	30		Cum	1	15.00	0.90	0.125	1.69		
30	46		Cum	1	16.00	0.90	0.125	1.80		
		School side drain near railway track								
0	15		Cum	1	15.00	1.05	0.1	1.58		
15	30		Cum	1	15.00	1.05	0.1	1.58		
		Culvert								
		near railway track	Cum	1	6.10	2.00	0.15	1.83		
		Defence layout 5th cross Road	Cum	1	9.00	2.00	0.15	2.70		
		Balaji layout								
		6th cross								
0	15		Cum	1	15.00	1.10	0.10	1.65		
15	30		Cum	1	15.00	1.10	0.10	1.65		
30	45		Cum	1	15.00	1.10	0.10	1.65		
45	60		Cum	1	15.00	1.10	0.10	1.65		
60	75		Cum	1	15.00	1.10	0.10	1.65		
75	90		Cum	1	15.00	1.10	0.10	1.65		
90	105		Cum	1	15.00	1.10	0.10	1.65		
105	120		Cum	1	15.00	1.10	0.10	1.65		
120	128		Cum	1	8.00	1.10	0.10	0.88		
		5th main road								
0	15		Cum	1	15.00	0.60	0.15	1.35		
15	27.5		Cum	1	12.50	0.60	0.15	1.13		
33.2	60	(27.5 to 33.2 Culvert	Cum	1	26.80	0.60	0.15	2.41		
67	96.5	(60 to 67 Culvert)	Cum	1	29.50	0.60	0.15	2.66		
102	129.7	(96.5 to 101.7)Culvert	Cum	1	28.00	0.60	0.15	2.52		
134	149.4	(129.7 to 134.4 Culvert	Cum	1	15.00	0.60	0.15	1.35		
149	164.4		Cum	1	15.00	0.60	0.15	1.35		
		6th main to upto 10th cross								
0	15		Cum	1	15.00	1.10	0.10	1.65		
15	30		Cum	1	15.00	1.10	0.10	1.65		
30	45		Cum	1	15.00	1.10	0.10	1.65		
45	60		Cum	1	15.00	1.10	0.10	1.65		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No.	Length (m)	Breadth (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
		Bottom Raft								
		1st cross								
		Left Side								
0	15		Cum	1	15.00	1.90	1.15	2.03		
15	23		Cum	1	8.00	1.90	1.15	1.08		
		Walls								
		Left Side								
0	15		Cum	2	15.00	1.15	1.6	2.70		
15	23		Cum	2	8.00	1.15	1.65	1.56		
		2nd cross								
		Bottom Raft								
		Left Side								
1	15		Cum	1	15.00	1.90	1.15	2.03		
15	31		Cum	1	15.00	1.90	1.15	2.03		
31	41		Cum	1	11.00	1.90	1.15	1.35		
		Right Side								
1	15		Cum	1	15.00	1.90	1.15	2.03		
15	35		Cum	1	21.00	1.90	1.15	2.70		
		Walls								
		Left Side								
1	15		Cum	2	15.00	1.15	1.65	2.53		
15	31		Cum	2	15.00	1.15	1.6	2.70		
31	41		Cum	2	11.00	1.15	1.6	1.80		
		Right Side								
0	15		Cum	2	15.00	1.15	1.65	2.53		
15	30.5		Cum	2	15.50	1.15	1.6	2.79		
		3rd Cross Road								
		Bottom Raft								
		Left Side								
0	15		Cum	1	15.00	1.90	1.15	2.03		
15	31		Cum	1	15.00	1.90	1.15	2.03		
31	45		Cum	1	15.00	1.90	1.15	2.03		
45	54		Cum	1	9.00	1.90	1.15	1.22		
		Right Side								
0	15		Cum	1	15.00	1.90	1.15	2.03		
15	31		Cum	1	15.00	1.90	1.15	2.03		
31	46		Cum	1	16.00	1.90	1.15	2.16		
		Walls								
		Left Side								
0	15		Cum	2	15.00	1.15	1.65	2.53		
15	31		Cum	2	15.00	1.15	1.6	2.70		
31	45		Cum	2	15.00	1.15	1.6	2.70		
45	54		Cum	2	9.00	1.15	1.6	1.62		
		Right Side								
0	15		Cum	2	15.00	1.15	1.65	2.53		
15	31		Cum	2	15.00	1.15	1.6	2.70		
31	46		Cum	2	16.00	1.15	1.6	2.88		
		4th Cross road								
		Bottom Raft								
		Left Side								
0	15		Cum	1	15.00	1.90	1.15	2.03		
15	31		Cum	1	15.00	1.90	1.15	2.03		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
30	45		Cum	1	15.00	0.90	0.15	2.03		
45	54		Cum	1	9.00	0.90	0.15	1.22		
		Right Side								
0	15		Cum	1	15.00	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.15	2.03		
30	46		Cum	1	16.00	0.90	0.15	2.16		
		Walls								
		Left Side								
0	15		Cum	2	15.00	0.15	0.65	2.93		
15	30		Cum	2	15.00	0.15	0.6	2.70		
30	45		Cum	2	15.00	0.15	0.6	2.70		
45	54		Cum	2	9.00	0.15	0.6	1.62		
		Right Side								
0	15		Cum	2	15.00	0.15	0.65	2.93		
15	30		Cum	2	15.00	0.15	0.6	2.70		
30	46		Cum	2	16.00	0.15	0.6	2.88		
		School side drain near railway track								
		Bottom Raft								
0	15		Cum	1	15.00	1.05	0.15	2.36		
15	30		Cum	1	15.00	1.05	0.15	2.36		
		Walls								
0	15		Cum	2	15.00	0.15	1.1	4.95		
15	30		Cum	2	15.00	0.15	1.1	4.95		
						Sub Total		109.16		
		Balaji layout								
		Bottom Raft								
		6th cross								
0	15		Cum	1	15.00	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.15	2.03		
60	75		Cum	1	15.00	0.90	0.15	2.03		
75	90		Cum	1	15.00	0.90	0.15	2.03		
90	105		Cum	1	15.00	0.90	0.15	2.03		
105	120		Cum	1	15.00	0.90	0.15	2.03		
120	128		Cum	1	8.00	0.90	0.15	1.08		
		Walls								
0	15		Cum	2	15.00	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.60	2.70		
105	120		Cum	2	15.00	0.15	0.65	2.93		
120	128		Cum	2	8.00	0.15	0.65	1.56		
		5th main road								
		Bottom Raft								
0	15		Cum	1	15.00	0.60	0.20	1.80		
15	27.5		Cum	1	12.50	0.60	0.20	1.50		
33.2	60	(27.5 to 33.2 Culvert	Cum	1	26.80	0.60	0.20	3.22		
67	96.5	(60 to 67 Culvert)	Cum	1	29.50	0.60	0.20	3.54		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		Behind anjaneya swami temple, Kodigehalli								
0	15		Sqm	1	15.00	4.55		68.25		
15	30		Sqm	1	15.00	3.65		54.75		
30	46.6		Sqm	1	16.60	3.95		65.57		
		Cross Road								
0	6.5		Sqm	1	6.50	1.40		9.10		
		4th Cross Road Kodigehalli								
0	19		Sqm	1	19.00	3.85		73.15		
19	34		Sqm	1	15.00	3.30		49.50		
34	50		Sqm	1	16.00	3.80		60.80		
		B.Saroja devi road,Kodigehalli Village								
0	15		Sqm	1	15.00	3.75		56.25		
15	30		Sqm	1	15.00	3.30		49.50		
30	45		Sqm	1	15.00	2.95		44.25		
45	64		Sqm	1	19.00	2.40		45.60		
		2nd Cross Kodigehalli								
0	15		Sqm	1	15.00	3.20		48.00		
15	30		Sqm	1	15.00	2.80		42.00		
30	49.6		Sqm	1	19.60	2.55		49.98		
		10th Main Maruthinagar								
		10th A Cross								
0	17.2		Sqm	1	17.20	5.30		91.16		
		10th C Cross								
0	15		Sqm	1	15.00	5.80		87.00		
15	27.7		Sqm	1	12.70	6.25		79.38		
		bb nagar bus stop opp rd								
0	5.6		Sqm	1	5.60	1.70		9.52		
5.6	20.4		Sqm	1	14.80	2.00		29.60		
0	11		Sqm	1	11.00	2.60		28.60		
		bb nagar bus stop opp rd								
0	6		Sqm	1	6.00	2.20		13.20		
6	12.6		Sqm	1	6.60	2.30		15.18		
		Road Portion								
		5th Cross								
0	15		Sqm	1	15.00	4.40		66.00		
15	30		Sqm	1	15.00	4.40		66.00		
30	43.3		Sqm	1	13.30	4.25		56.53		
		4th Cross								
0	15		Sqm	1	15.00	4.05		60.75		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
15	30		Sqm	1	15.00	4.15		62.25		
30	45		Sqm	1	15.00	4.65		69.75		
45	60		Sqm	1	15.00	4.50		67.50		
60	75		Sqm	1	15.00	4.20		63.00		
75	92		Sqm	1	17.00	5.05		85.85		
92.6	94.4	Culvert								
94.4	107.4		Sqm	1	13.00	4.00		52.00		
107	117		Sqm	1	9.60	4.00		38.40		
117	119.2	Culvert								
119	134		Sqm	1	14.80	4.10		60.68		
134	149		Sqm	1	14.80	3.90		57.72		
149	158		Sqm	1	8.80	3.80		33.44		
		9th Cross								
0	15		Sqm	1	15.00	4.15		62.25		
15	28		Sqm	1	13.00	4.15				
		2nd Cross near Kannuramma temple								
0	10		Sqm	1	10.00	4.35		43.50		
								Total Qty	4955.99	102.08	505907.46
								Tender Qty	5556.35		
Item no.36		Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as per specifications.and as per the directions of the Engineer-in-charge of the work .								
		8th main road side park								
		Front Side	Cum	1	86.50	0.75	0.75	48.66		
		left side	Cum	1	3.50	0.75	0.75	1.97		
		Back side	Cum	1	87.00	0.75	0.75	48.94		
		Right side	Cum	1	7.00	0.75	0.75	3.94		
		9th cross near indira canteen								
		Front Side	Cum	1	105.00	0.75	0.75	59.06		
		Right side	Cum	1	16.00	0.75	0.75	9.00		
		Hanumayya layout								
		SSM Wall								
		culverts								
		near railway track	Cum	2	6.10	0.60	1.1	8.05		
		Defence layout 5th cross Road	Cum	2	9.00	0.60	0.90	9.72		
		Lottegollahalli								
		culverts								
		2nd cross Lottegollahalli								
		Left Side								
			Cum	2	4.50	0.60	0.75	4.05		
		Right side								
			Cum	2	4.50	0.60	0.75	4.05		
		SSM Wall	Cum							

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
		Damaged SSM Qnty								
		Kodigehalli main road glass hornet to shahid motors								
20	44.5		Cum	2	24.50	0.45	0.80	17.64		
59.1	71		Cum	2	11.90	0.45	0.80	8.57		
							Total Qty	223.64	4748.90	1062055.87
							Tender Qty	382.5802		
Item no.37		Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work .								
		8th main road side park								
		Front Side	Cum	1	86.50	0.45	0.6	23.36		
		left side	Cum	1	3.50	0.45	0.6	0.95		
		Back side	Cum	1	87.00	0.45	0.6	23.49		
		Right side	Cum	1	7.00	0.45	0.6	1.89		
		9th cross near indira canteen								
		Front Side	Cum	1	62.00	0.45	0.45	12.56		
			Cum	1	43.00	0.45	0.6	11.61		
		Right side	Cum	1	16.00	0.45	0.6	4.32		
		For pole insertion		121	0.45	0.45	-0.45	-11.03		
							Total Qty	67.14	5676.67	381125.24
							Tender Qty	108.57		
Item no.38		Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work .								
		Park								
		8th main road side park								
		Front Side	Sqm	1	86.50		1.35	116.78		
		left side	Sqm	1	3.50		1.35	4.73		
		Back side	Sqm	1	87.00		1.35	117.45		
		Right side	Sqm	1	7.00		1.35	9.45		
		9th cross near indira canteen								
		Front Side	Sqm	1	62.00		1.2	74.40		
			Sqm	1	43.00		1.35	58.05		
		Right side	Sqm	1	16.00		1.35	21.60		
		Hanumayya layout								
		SSM Wall								
		Culverts								
			Sqm	2	6.10		1.1	13.42		
		Defence layout 5th cross Road	Sqm	2	9.00		0.90	16.20		
		Lottegollahalli								
		culverts								

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
		2nd cross Lottegollahalli								
		Left Side								
			Sqm	2	4.50		0.75	6.75		
		Right side								
			Sqm	2	4.50		0.75	6.75		
		Kodigehalli main road								
0	15		Sqm	2	15.00		1.00	30.00		
15	30		Sqm	2	15.00		1.00	30.00		
30	45		Sqm	2	15.00		1.00	30.00		
45	60		Sqm	2	15.00		1.00	30.00		
60	75		Sqm	2	15.00		1.00	30.00		
75	91		Sqm	2	16.00		1.00	32.00		
							Total Qty	**627.57**	**110.02**	**69045.25**
							Tender Qty	**773.59**		
Item no.39		Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.530 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work .								
		Coping								
		Park								
		8th main road side park								
		Front Side	Cum	1	86.50	0.45	0.10	3.89		
		left side	Cum	1	3.50	0.45	0.10	0.16		
		Back side	Cum	1	87.00	0.45	0.10	3.92		
		Right side	Cum	1	7.00	0.45	0.10	0.32		
		9th cross near indira canteen								
		Front Side	Cum	1	62.00	0.45	0.10	2.79		
			Cum	1	43.00	0.45	0.10	1.94		
		Right side	Cum	1	16.00	0.45	0.10	0.72		
		For pole insertion								
		Park								
		8th main road side park								
		Front Side	Cum	34	0.45	0.45	0.45	3.10		
		left side	Cum	1	0.45	0.45	0.45	0.09		
		Back side	Cum	36	0.45	0.45	0.45	3.28		
		Right side	Cum	2	0.45	0.45	0.45	0.18		
		9th cross near indira canteen								
		Front Side	Cum	44	0.45	0.45	0.45	4.01		
		Right side	Cum	5	0.45	0.45	0.45	0.46		
		Hanumayya layout								
		Culverts								
			Cum	2	6.10	0.60	0.1	0.73		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		Defence layout 5th cross Road	Cum	2	9.00	0.60	0.1	1.08		
		Slope Concrete								
		1st cross								
		Left Side								
0	15		Cum	1	15.00	0.20	0.1	0.30		
15	23		Cum	1	8.00	0.20	0.1	0.16		
		2nd cross								
		Left Side								
0	15		Cum	1	15.00	0.20	0.1	0.30		
15	30		Cum	1	15.00	0.20	0.1	0.30		
30	40		Cum	1	10.00	0.20	0.1	0.20		
		Right Side								
0	15		Cum	1	15.00	0.20	0.1	0.30		
15	30.5		Cum	1	15.50	0.20	0.1	0.31		
		3rd Cross Road								
		Left Side								
0	15		Cum	1	15.00	0.20	0.1	0.30		
15	30		Cum	1	15.00	0.20	0.1	0.30		
30	45		Cum	1	15.00	0.20	0.1	0.30		
45	54		Cum	1	9.00	0.20	0.1	0.18		
		Right Side								
0	15		Cum	1	15.00	0.20	0.1	0.30		
15	30		Cum	1	15.00	0.20	0.1	0.30		
30	46		Cum	1	16.00	0.20	0.1	0.32		
		4th Cross road								
		Left Side								
0	15		Cum	1	15.00	0.20	0.1	0.30		
15	30		Cum	1	15.00	0.20	0.1	0.30		
30	45		Cum	1	15.00	0.20	0.1	0.30		
45	54		Cum	1	9.00	0.20	0.1	0.18		
		Right Side								
0	15		Cum	1	15.00	0.20	0.1	0.30		
15	30		Cum	1	15.00	0.20	0.1	0.30		
30	46		Cum	1	16.00	0.20	0.1	0.32		
		School side drain near								
0	15		Cum	1	15.00	0.20	0.1	0.30		
15	30		Cum	1	15.00	0.20	0.1	0.30		
		culverts								
		2nd cross Lottegollahalli								
		Left Side								
			Cum	2	4.50	0.60	0.10	0.54		
		Right side								
			Cum	2	4.50	0.60	0.10	0.54		
		Slope Concrete								
		Lottegollahalli								

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
		2nd cross Lottegollahalli(LJ Iyengarbakery)								
		Left Side								
0	15		Cum	1	15.00	0.20	0.15	0.45		
15	30		Cum	1	15.00	0.20	0.15	0.45		
30	45		Cum	1	15.00	0.20	0.15	0.45		
45	57.5		Cum	1	12.50	0.20	0.15	0.38		
62	77	(57.5 to 62 Culvert)	Cum	1	15.00	0.20	0.15	0.45		
77	92		Cum	1	15.00	0.20	0.15	0.45		
92	109		Cum	1	17.00	0.20	0.15	0.51		
		Right side								
0	15		Cum	1	15.00	0.20	0.15	0.45		
15	30		Cum	1	15.00	0.20	0.15	0.45		
30	45		Cum	1	15.00	0.20	0.15	0.45		
45	57.5		Cum	1	12.50	0.20	0.15	0.38		
62	77	(57.5 to 62 Culvert)	Cum	1	15.00	0.20	0.15	0.45		
77	92		Cum	1	15.00	0.20	0.15	0.45		
92	112		Cum	1	20.00	0.20	0.15	0.60		
		4th Cross road Lhs(RMV cluster)								
		Left Side								
0	15		Cum	1	15.00	0.20	0.15	0.45		
15	30		Cum	1	15.00	0.20	0.15	0.45		
30	45		Cum	1	15.00	0.20	0.15	0.45		
45	57		Cum	1	12.00	0.20	0.15	0.36		
		1st cross								
		Left Side								
0	15		Cum	1	15.00	0.30	0.15	0.68		
15	30		Cum	1	15.00	0.30	0.15	0.68		
30	45		Cum	1	15.00	0.30	0.15	0.68		
45	60		Cum	1	15.00	0.30	0.15	0.68		
65	85.5	(60 to 65 Culvert)	Cum	1	20.50	0.30	0.15	0.92		
88	103	(85.5 to 88 Culvert)	Cum	1	15.00	0.30	0.15	0.68		
103	118		Cum	1	15.00	0.30	0.15	0.68		
118	120		Cum	1	2.00	0.30	0.15	0.09		
		Right side								
0	15		Cum	1	15.00	0.30	0.15	0.68		
15	30		Cum	1	15.00	0.30	0.15	0.68		
30	45		Cum	1	15.00	0.30	0.15	0.68		
45	60		Cum	1	15.00	0.30	0.15	0.68		
60	75		Cum	1	15.00	0.30	0.15	0.68		
75	90		Cum	1	15.00	0.30	0.15	0.68		
90	105		Cum	1	15.00	0.30	0.15	0.68		
105	117.7		Cum	1	12.70	0.30	0.15	0.57		
		Kodigehalli main road glass hornet to shahid motors								
0	15		Cum	2	15.00	0.45	0.075	1.01		
15	30		Cum	2	15.00	0.45	0.075	1.01		
30	45		Cum	2	15.00	0.45	0.075	1.01		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
45	60		Cum	2	15.00	0.45	0.075	1.01		
60	75		Cum	2	15.00	0.45	0.075	1.01		
75	91		Cum	2	16.00	0.45	0.075	1.08		
		Culvert								
			Cum	2	4.80	0.60	0.10	0.58		
		near ganesh Temple								
0	15		Cum	1	15.00	0.20	0.10	0.30		
15	32.3		Cum	1	17.30	0.20	0.10	0.35		
		Glass factory backside Raod								
		Left Side								
0	15		Cum	1	15.00	0.20	0.10	0.30		
15	36		Cum	1	21.00	0.20	0.10	0.42		
		Right Side								
0	15		Cum	1	15.00	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.10	0.30		
		dee enclave to trio school (kodigehalli mn road)								
0	15		Cum	1	15.00	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.10	0.30		
30	40		Cum	1	10.00	0.20	0.10	0.20		
							Total Qty	**62.12**	**6171.18**	**383339.82**
							Tender Qty	**80.27**		
Item no.41		Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete. and as per the directions of the Engineer-in-charge of the work .								
		Balaji layout								
		6th main to upto 10th cross								
0	15		No	1	15.00		/0.45	33.00		
15	30		No	1	15.00		/0.45	33.00		
30	45		No	1	15.00		/0.45	33.00		
45	60		No	1	15.00		/0.45	33.00		
60	75		No	1	15.00		/0.45	33.00		
75	90		No	1	15.00		/0.45	33.00		
90	105		No	1	15.00		/0.45	33.00		
105	121		No	1	16.00		/0.45	36.00		
		11th cross Hoysala								
0	15		No	1	15.00		/0.45	33.00		
15	30		No	1	15.00		/0.45	33.00		
30	45		No	1	15.00		/0.45	33.00		
45	60		No	1	15.00		/0.45	33.00		
70	85		No	1	15.00		/0.45	33.00		
85	100		No	1	15.00		/0.45	33.00		
100	115		No	1	15.00		/0.45	33.00		
115	130		No	1	15.00		/0.45	33.00		
130	145		No	1	15.00		/0.45	33.00		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
145	160		No	1	15.00		/0.45	33.00		
160	175		No	1	15.00		/0.45	33.00		
175	190		No	1	15.00		/0.45	33.00		
		6th cross								
0	15		No	1	15.00		/0.45	33.00		
15	30		No	1	15.00		/0.45	33.00		
30	45		No	1	15.00		/0.45	33.00		
45	60		No	1	15.00		/0.45	33.00		
60	75		No	1	15.00		/0.45	33.00		
75	90		No	1	15.00		/0.45	33.00		
90	105		No	1	15.00		/0.45	33.00		
105	120		No	1	15.00		/0.45	33.00		
120	128		No	1	8.00		/0.45	18.00		
		6th main 10th cross								
0	15		No	1	15.00		/0.45	33.00		
15	30		No	1	15.00		/0.45	33.00		
30	45		No	1	15.00		/0.45	33.00		
45	60		No	1	15.00		/0.45	33.00		
60	80		No	1	20.00		/0.45	44.00		
		6th main 10th cross to 11th Cross								
0	20		No	1	20.00		/0.45	44.00		
25	33.2		No	1	8.20		/0.45	18.00		
		Missing kerb stone								
			No	52				52.00		
		For Road Kerb								
		Culvert to kodigehalli Circle								
		LHS	Nos	1	41.40		/0.45	92.00		
		RHS	Nos	1	57.70		/0.45	128.00		
		Culvert to Underpass								
		RHS	Nos	1	125.40		/0.45	279.00		
		LHS	Nos	1	119.00		/0.45	264.00		
							Total Qty	**1998.00**	**355.00**	**709290.00**
							Tender Qty	**3091.00**		
Item no.42		KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (P.No.182, I.No. 24.1 of PW,P&IWTD SR 2016-17)								
		For Kerb Painting								
		Culvert to kodigehalli Circle								
		LHS	Sqm	1	41.40		0.35	14.49		
		RHS	Sqm	1	57.70		0.35	20.20		
		Culvert to Underpass								
		RHS	Sqm	1	125.40		0.35	43.89		
		LHS	Sqm	1	119.00		0.35	41.65		
							Total Qty	**120.23**	**68.05**	**8181.31**
							Tender Qty	**486.85**		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
Item no.43		Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)								
		Chain Link Fancing								
		8th main road side park								
		Front Side	Rmt	34			2.50	85.00		
		left side	Rmt	1			2.50	2.50		
		Back side	Rmt	36			2.50	90.00		
		Right side	Rmt	2			2.50	5.00		
		9th cross near indira canteen								
		Front Side	Rmt	44			2.50	110.00		
		Right side	Rmt	5			2.50	12.50		
								Total Qty	**305.00**	**928.91**	**283317.55**
								Tender Qty	**440.00**		
Item no.44		Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint								
		Chain Link Fancing								
		8th main road side park								
		Front Side	Sqm	1	82.15		2.00	164.30		
		left side	Sqm	1	3.50		2.00	7.00		
		Back side	Sqm	1	87.00		2.00	174.00		
		Right side	Sqm	1	7.00		2.00	14.00		
		9th cross near indira canteen								
		Front Side	Sqm	1	105.00		2.00	210.00		
		Right side	Sqm	1	11.60		2.00	23.20		
								Total Qty	**592.50**	**747.44**	**442858.20**
								Tender Qty	**957.00**		
Item no.45		Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint.								
		Chain Link Fancing								
		8th main road side park								
		Front Side	m	2	74.4			148.80		
		left side	m	2	3.4			6.80		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
		Back side	m	2	82.25			164.50		
		Right side	m	2	6.75			13.50		
		9th cross near indira canteen								
		Front Side	m	2	100.50			201.00		
		Right side	m	2	9.60			19.20		
							Total Qty	**553.80**		
							Tender Qty	**469.00**		
							Qty upto 125%	**553.80**	**367.48**	**203510.87**
		Basic rate	324							
		6% weightage	19.44							
		Total Rs.	343.44							
		(+7%)TP	24.0408							
		Net Total Rs.	**367.48**							
Item no. 47		Removing and resetting of footpath slab and as per the directions of the Engineer-in-charge of the work .								
		1t Main Gvt School Road								
		Left side								
12	22		Sqm	1	10.00	1.20		12.00		
26	30.5		Sqm	1	4.50	1.20		5.40		
42	53		Sqm	1	11.00	1.20		13.20		
73	75		Sqm	1	2.00	1.20		2.40		
95	99		Sqm	1	4.00	1.20		4.80		
121	125.7		Sqm	1	4.70	1.20		5.64		
144	148.5		Sqm	1	4.50	1.20		5.40		
168	172.9		Sqm	1	4.90	1.20		5.88		
		Right side								
18	33		Sqm	1	15.00	1.20		18.00		
42	53		Sqm	1	11.00	1.20		13.20		
66	73		Sqm	1	7.00	1.20		8.40		
85	94.3		Sqm	1	9.30	1.20		11.16		
96	106		Sqm	1	10.00	1.20		12.00		
123	127.8		Sqm	1	4.80	1.20		5.76		
152	163		Sqm	1	11.00	1.20		13.20		
185	189.9		Sqm	1	4.90	1.20		5.88		
		Hanumaiah Layout Main Road								
		Left side								
18	23.8		Sqm	1	5.80	0.90		5.22		
31	38		Sqm	1	7.00	0.90		6.30		
42.5	47.9		Sqm	1	5.40	0.90		4.86		
55	62		Sqm	1	7.00	0.90		6.30		
71	76.1		Sqm	1	5.10	0.90		4.59		
88	96		Sqm	1	8.00	0.90		7.20		
108	113.2		Sqm	1	5.20	0.90		4.68		
136	140.9		Sqm	1	4.90	0.90		4.41		
168	174		Sqm	1	6.00	0.90		5.40		
202	215		Sqm	1	13.00	0.90		11.70		
258	263.1		Sqm	1	5.10	0.90		4.59		

Scanned by CamScanner

Chainage		Description of Item	Unit	No	Length	Breadt	Depth	Quantity	Rate	Amount
From	To				(m)	(m)	(m)		Rs	Rs
278	285		Sqm	1	7.00	0.90		6.30		
302	306.9		Sqm	1	5.40	0.90		4.86		
355	363.1		Sqm	1	8.10	0.90		7.29		
388	394.2		Sqm	1	6.20	0.90		5.58		
402	407		Sqm	1	5.00	0.90		4.50		
428	433.1		Sqm	1	5.10	0.90		4.59		
467	472.3		Sqm	1	5.30	0.90		4.77		
497	502.6		Sqm	1	5.60	0.90		5.04		
		Right side								
21	26.9		Sqm	1	5.90	0.90		5.31		
52	57.8		Sqm	1	5.80	0.90		5.22		
91	96.5		Sqm	1	5.50	0.90		4.95		
106	111.2		Sqm	1	5.20	0.90		4.68		
147	152.4		Sqm	1	5.40	0.90		4.86		
168	173.5		Sqm	1	5.50	0.90		4.95		
208	213.5		Sqm	1	5.50	0.90		4.95		
261	269		Sqm	1	8.00	0.90		7.20		
297	302.5		Sqm	1	5.50	0.90		4.95		
311	316.1		Sqm	1	5.10	0.90		4.59		
358	363.1		Sqm	1	5.10	0.90		4.59		
393	398.4		Sqm	1	5.40	0.90		4.86		
406	411.2		Sqm	1	5.20	0.90		4.68		
439	444		Sqm	1	5.00	0.90		4.50		
472	477.6		Sqm	1	5.60	0.90		5.04		
504	509.5		Sqm	1	5.50	0.90		4.95		
		1st Cross Tata Nagar(BESCOM Office Loop Road)								
		Left side								
12	17		sqm	1	5.00	0.90		4.50		
26	30.8		sqm	1	4.80	0.90		4.32		
52	56.8		sqm	1	4.80	0.90		4.32		
81	85.6		sqm	1	4.60	0.90		4.14		
		Right side								
9	13.8		sqm	1	4.80	0.90		4.32		
25	30		sqm	1	5.00	0.90		4.50		
53	57.9		sqm	1	4.90	0.90		4.41		
78	82.4		sqm	1	4.40	0.90		3.96		
		Kodigehalli main road glass hornet to shahid								
0	15		Sqm	1	15.00	1.20		18.00		
15	26.5		Sqm	1	11.50	1.20		13.80		
32	45		Sqm	1	13.00	1.20		15.60		
45	60		Sqm	1	15.00	1.20		18.00		
60	75		Sqm	1	15.00	1.20		18.00		
75	90		Sqm	1	15.00	1.20		18.00		
90	105		Sqm	1	15.00	1.20		18.00		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
105	120		Sqm	1	15.00	1.20		18.00		
120	135		Sqm	1	15.00	1.20		18.00		
135	150		Sqm	1	15.00	1.20		18.00		
160	165		Sqm	1	5.50	1.20		6.60		
169	180		Sqm	1	11.00	1.20		13.20		
183	190		Sqm	1	7.00	1.20		8.40		
202	210		Sqm	1	8.00	1.20		9.60		
210	225		Sqm	1	15.00	1.20		18.00		
225	240		Sqm	1	15.00	1.20		18.00		
240	249		Sqm	1	9.00	1.20		10.80		
							Total Qty	623.25	141.78	88364.39
							Tender Qty	626.52		
Item no.48		Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. and as per the directions of the Engineer-in-charge of the work .								
		Kodigehalli main road glass hornet to shahid motors								
8	14		Cum	2	6.00	0.45	0.80	4.32		
26	29		Cum	2	3.00	0.45	0.80	2.16		
30	34.1		Cum	2	4.10	0.45	0.80	2.95		
42	49.2		Cum	2	7.20	0.45	0.80	5.18		
63	69		Cum	2	6.00	0.45	0.80	4.32		
81	91		Cum	2	10.00	0.45	0.80	7.20		
							Total Qty	26.14	401.67	10498.05
							Tender Qty	27.36		
Item no.49		Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as per specifications. and as per the directions of the Engineer-in-charge of the work .								
		SSM Wall								
		Kodigehalli main road glass hornet to shahid motors								
		Available stone								
0	18		Cum	2	18.00	0.45	0.80	12.96		
36.1	57		Cum	2	20.90	0.45	0.80	15.05		
71	89		Cum	2	18.00	0.45	0.80	12.96		
							Total Qty	40.97	2979.54	122071.75
							Tender Qty	41.04		

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
Item no.52		Construction of granular sub-base by providing close graded crushed stone aggregates of granite / trap / basalt material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method. For Grading II Materiall(P.No.155, I.No.20.4.2 of PW,P&IWTD S.R 2016-17)								
		Culvert to kodigehalli Circle	Cum	1	50.50	16.80	0.40	339.36		
		Culvert to Underpass	Cum	1	138.30	16.10	0.40	890.65		
							Total Qty	**1230.01**		
							Tender Qty	**254.10**		
							Qty upto 125%	**317.63**	**1781.83**	565953.75
							Qty Above 125%	**912.39**	**1781.83**	1625718.53
		Basic rate	1571							
		6% weightage	94.26							
		Total Rs.	1665.26							
		(+7%)TP	116.5682							
		Net Total Rs.	**1781.828**							
E1		Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)								
		Culvert								
		Culvert to kodigehalli Circle								
		RHS	Sqm	1	5.30	1.20		6.36		
		Culvert to Underpass								
		RHS	Sqm	1	3.70	1.20		4.44		
		RHS	Sqm	1	5.30	1.20		6.36		
		RHS	Sqm	1	5.70	1.20		6.84		
		LHS	Sqm	1	5.00	1.20		6.00		
		LHS	Sqm	1	5.30	1.20		6.36		
		LHS	Sqm	1	4.10	1.20		4.92		
		LHS	Sqm	1	5.70	1.20		6.84		
							Total Qty	**48.12**	**5418.00**	**260714.16**
E2		Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)								
		Culvert to kodigehalli Circle								
		LHS	Sqm	1	41.40	0.90		37.26		
		RHS	Sqm	1	57.70	0.90		51.93		
		Culvert to Underpass								
		RHS	Sqm	1	125.40	0.90		112.86		
		LHS	Sqm	1	119.00	0.90		107.1		
		Missing Slab	Sqm	1	50.00	0.90		45		
							Total Qty	**354.15**	**2337.00**	**827648.55**

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
E3		Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members asshown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specifiocation. (P. No. 45 / I. No. 7.37 of CSR 2018-19)								
		8th main road side park	Sqm	1	4.35	2.1		9.14		
		8th main road side park	Sqm	1	4.4	2.1		9.24		
							Total	**18.38**	**3416.21**	**62772.87**
		Basic rate	3012							
		6% weightage	180.72							
		Total Rs.	3192.72							
		(+7%)TP	223.4904							
		Net Total Rs.	**3416.21**							
E4		KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (Page No. 123 Item No. 15.74 of SR 2018-19).								
		8th main road side park	Sqm	2	4.35	2.1		18.27		
		8th main road side park	Sqm	2	4.4	2.1		18.48		
							Total	**36.75**	**107.75**	**3959.78**
		Basic rate	95							
		6% weightage	5.7							
		Total Rs.	100.7							
		(+7%)TP	7.049							
		Net Total Rs.	**107.75**							
E5		KSRRB M800 Road markers/ Road stud , KSRRB M800-35. Supply and Installtion of Moulded Shank Raised Pavement Markers made of polycarbonate and ABS (Acrylonitrile Butadiene Styrene) moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering thje lens face and shall support a load of 16000 kg tested in accordance to Specifications of Category A of MORTH Circular No RW/NH/33023/10-97-DO III Dt 11.06.1997.The height, width and length shall not exceed 50mm, 100mm and 102 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree.The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19mm and height not less than 30mm)from the body is to be a minimum value of 500kg. Fixing will be by drilling holes on the road for the shanks to go inside, without ails and using epoxy resin based adhesive as per manufacture's recommendation and complete as directed by the engineer.(P.No-187,I No-24.41)								
		Road Studs along Road Length								

Scanned by CamScanner

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadt (m)	Depth (m)	Quantity	Rate Rs	Amount Rs
		Culvert to kodigehalli Circle	M	3	50.50			151.50		
		Culvert to Underpass	M	3	138.30			414.90		
			Nos			Sub		566.40		
		Provide Studs for every 3m along Road lenth								
		Number of Studs along Road Length			Total length/3			188.80		
		Total						188.80	382.23	72164.16
		Basic rate	337.00							
		Area weightage 6%	20.22							
		Total	357.22							
		(+7%)TP	25.01							
		Sub Total	382.23							
								Total construction Cost		104294737.80

JE W8 (WARD NO 8)

Assistant Executive Engineer
Kodigehalli Sub Division
Yelahanka Zone, B.B.M.P.
Bangalore.

ಕಾರ್ಯ ನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ವಿದ್ಯಾರಣ್ಯಪುರ ವಿಭಾಗ ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ ಬೆಂಗಳೂರು-5600

AE - W-09

Assistant Executive Engineer
Vidyaranyapura Sub Division
BBMP, Bangalore-97

Scanned by CamScanner